

| Pennsylvania Turnpike Commission - Tabulation of Bids |                 |                 | Green Acres Contracting Company  |                                 |               |
|---|-----------------|-----------------|--|---------------------------------|---------------|
|   | Contract Number |                 | 00-011-RCN9-C  | Scottsdale PA                   |               |
|   |                 |                 | GUIDE RAIL END TREATMENT UPDATES<br>btwn MP 10.4 and MP 56.3 in Beaver,<br>Butler & Allegheny Counties |                                 |               |
|   | Opening Date    |                 | 3/21/07, 11:00 AM  |                                 |               |
|   | Awarded to:     |                 | Green Acres Contracting  | Green Acres Contracting Company |               |
| Item  | Quantity        | Unit of Measure | Description  | Unit Price                      | Total Price   |
| 2203-0001   | 3,082           | CY              | CLASS 1 EXCAVATION   | \$ 39.00                        | \$ 120,198.00 |
| 2203-0040   | 155             | CY              | CLASS 1 EXCAVATION (ROCK)  | \$ 112.00                       | \$ 17,360.00  |
| 2204-0001   | 42              | CY              | CLASS 2 EXCAVATION   | \$ 125.00                       | \$ 5,250.00   |
| 4205-0100   | 38              | CY              | BORROW MATERIAL  | \$ 100.00                       | \$ 3,800.00   |
| 4491-0001   | 9,264           | SY              | SCARIFICATION, 6" DEPTH  | \$ 3.00                         | \$ 27,792.00  |
| 2601-7010   | 14              | LF              | 15" REINFORCED CONCRETE PIPE,<br>TYPE A, 15' - 2' FILL   | \$ 135.00                       | \$ 1,890.00   |
| 4601-7014   | 83              | LF              | 18" REINFORCED CONCRETE PIPE,<br>WITH SHOULDER REPAIR  | \$ 205.00                       | \$ 17,015.00  |
| 2605-0021   | 1               | EACH            | TYPE S INLET, CONDITION 2 BC   | \$ 2,295.00                     | \$ 2,295.00   |
| 4605-9000   | 2               | EACH            | PLUG EXISTING PIPE   | \$ 2,210.00                     | \$ 4,420.00   |
| 0608-0001   | 1               | LS              | MOBILIZATION   | \$ 112,000.00                   | \$ 112,000.00 |
| 2616-1201   | 1               | EACH            | CONCRETE END SECTIONS FOR 15"<br>PIPE  | \$ 1,000.00                     | \$ 1,000.00   |
| 2620-0402   | 2               | EACH            | TERMINAL SECTION, BRIDGE<br>CONNECTION   | \$ 125.00                       | \$ 250.00     |
| 4620-0501   | 175             | LF              | LOWER EXISTING GUIDE RAIL  | \$ 10.00                        | \$ 1,750.00   |
| 2620-0503   | 8,075           | LF              | REMOVE EXISTING GUIDE RAIL   | \$ 2.00                         | \$ 16,150.00  |
| 2620-0862   | 15              | EACH            | TYPE 2-S POST ANCHORAGE  | \$ 650.00                       | \$ 9,750.00   |
| 2620-0866   | 23              | EACH            | CONCRETE ANCHORAGE,<br>BACKSLOPE   | \$ 1,650.00                     | \$ 37,950.00  |
| 2620-1075   | 10,072          | LF              | TYPE 2-S GUIDE RAIL  | \$ 25.60                        | \$ 257,843.20 |
| 2620-1100   | 75              | LF              | TYPE 2-SC GUIDE RAIL   | \$ 35.00                        | \$ 2,625.00   |
| 2620-1255   | 47              | EACH            | VEHICLE ATTENUATING TERMINAL<br>END TREATMENT (V.A.T.E.T.), TYPE II                                    | \$ 2,500.00                     | \$ 117,500.00 |
| 2620-1256   | 2               | EACH            | VEHICLE ATTENUATING TERMINAL<br>END TREATMENT (V.A.T.E.T.), TYPE<br>III                                | \$ 3,000.00                     | \$ 6,000.00   |
| 4620-1299   | 2               | EACH            | REMOVE EXISTING VEHICLE<br>ATTENUATING TERMINAL END<br>TREATMENT (V.A.T.E.T.)                          | \$ 800.00                       | \$ 1,600.00   |
| 2620-1530   | 4               | EACH            | TYPE 2-S APPROACH END<br>TRANSITION, TYPE A  | \$ 1,600.00                     | \$ 6,400.00   |
| 2620-1535   | 1               | EACH            | TYPE 2-S APPROACH END<br>TRANSITION, TYPE B  | \$ 1,600.00                     | \$ 1,600.00   |
| 2620-2000   | 663             | EACH            | DRILLED POST HOLES   | \$ 1.00                         | \$ 663.00     |
| 2623-1001   | 3               | EACH            | ABUTMENT TRANSITION PIECE,<br>TYPE I   | \$ 10,000.00                    | \$ 30,000.00  |
| 2623-2001   | 58              | LF              | CONCRETE SAFETY WALL   | \$ 375.00                       | \$ 21,750.00  |

| <b>Awarded to:</b> Green Acres Contracting |                 |                        | Green Acres Contracting Company                       |                   |                        |
|--|-----------------|------------------------|---|-------------------|------------------------|
| <b>Item</b>                                | <b>Quantity</b> | <b>Unit of Measure</b> | <b>Description</b>                                    | <b>Unit Price</b> | <b>Total Price</b>     |
| 4636-0100                                  | 68              | LF                     | REMOVE BITUMINOUS CURB                                | \$ 15.00          | \$ 1,020.00            |
| 4636-0110                                  | 950             | LF                     | REMOVE BITUMINOUS ROLL UP CURB                        | \$ 15.00          | \$ 14,250.00           |
| 4802-0001                                  | 2,532           | CY                     | TOPSOIL FURNISHED AND PLACED                          | \$ 67.00          | \$ 169,644.00          |
| 2804-0013                                  | 502             | LB                     | SEEDING AND SOIL SUPPLEMENTS - FORMULA D              | \$ 10.00          | \$ 5,020.00            |
| 2804-0102                                  | 75              | LB                     | SEEDING AND SOIL SUPPLEMENTS - FORMULA BT-1           | \$ 18.00          | \$ 1,350.00            |
| 2805-0030                                  | 10,514          | SY                     | MULCHING-BONDED FIBER MATRIX                          | \$ 1.00           | \$ 10,514.00           |
| 4805-0031                                  | 1,040           | SY                     | BONDED FIBER MATRIX, STABILIZED                       | \$ 4.00           | \$ 4,160.00            |
| 2845-0001                                  | ---             | PDA                    | EROSION AND SEDIMENTATION CONTROL DURING CONSTRUCTION |                   | \$ 8,000.00            |
| 2850-0022                                  | 68              | SY                     | ROCK LINING, CLASS R-4                                | \$ 50.00          | \$ 3,400.00            |
| 2865-0001                                  | 4,490           | LF                     | SILT BARRIER FENCE, 18" HEIGHT                        | \$ 5.00           | \$ 22,450.00           |
| 2901-0001                                  | 1               | LS                     | MAINTENANCE AND PROTECTION OF TRAFFIC                 | \$ 100,000.00     | \$ 100,000.00          |
| 2901-0203                                  | 4               | EACH                   | ARROW PANEL   | \$ 3,000.00       | \$ 12,000.00           |
| 2901-0500                                  | 4               | EACH                   | PORTABLE CHANGEABLE MESSAGE SIGN                      | \$ 8,000.00       | \$ 32,000.00           |
| 2901-0501                                  | 4               | EACH                   | SHADOW VEHICLE WITH TRUCK MOUNTED ATTENUATOR (TMA)    | \$ 4,500.00       | \$ 18,000.00           |
| 2931-0001                                  | 33              | SF                     | POST MOUNTED SIGN, TYPE B                             | \$ 50.00          | \$ 1,650.00            |
| 4932-0001                                  | 1               | EACH                   | RELOCATION OF EXISTING POST MOUNTED SIGN, TYPE C      | \$ 1,250.00       | \$ 1,250.00            |
| 4934-0001                                  | 1               | EACH                   | RELOCATION OF EXISTING POST MOUNTED SIGN, TYPE E      | \$ 2,250.00       | \$ 2,250.00            |
| 2006-0001                                  | 4               | EACH                   | CALL BOX FOUNDATION                                   | \$ 1,500.00       | \$ 6,000.00            |
|  |                 |                        | <b>TOTAL</b>  |                   | <b>\$ 1,237,809.20</b> |
|  |                 |                        | Bid Bond  |                   | \$ 61,890.46           |